

	ARCON DESIGN CONSULTANTS			
	ARCHITECTURE INTERIORS LANDSCAPE			
	Tel:9419196076 , 8825000036			
	Email:arconsjk@gmail.com			
	Address:57 A/B, Gandhi Nagar Jammu-Tawi			
PROJECT - PROFORMA INVOICE FOR HEXAMED DIAGNOSTICS AT CHANNI HIMMAT, JAMMU				
BILL OF QUANTITIES				
RECEPTION AREA				
S.No	Item Description	Area	Rate	Amount
A	ELEVATION	138sq.ft	900/sq.ft	1,24,200
1	Base of wall panelling in 16.50mm MDF of Century Prowood or Action Tesa company bolted with the help of sawthread screws of best quality on base of panelling.			
2	Top finish will include PU Paint on wall panels (as per design) laminate finish with metal profiles and aluminium profiles for lighting and pu painted louvers/ Charcoal louvers on the same wall (as per design).			
B	ELEVATION	199sq.ft	900/sq.ft	1,79,100
1	Base of wall panelling in 16.50mm MDF of Century Prowood or Action Tesa company bolted with the help of sawthread screws of best quality on base of panelling.			
2	Glass shelves of 8mm supported by stainless steel brackets			
C	ELEVATION	154sq.ft	900/sq.ft	1,38,600
1	Base of wall panelling in 16.50mm MDF of Century Prowood or Action Tesa company bolted with the help of sawthread screws of best quality on base of panelling.			
2	Top finish will include premium quality wallpaper on the background. Glass Shelves of 8mm (as per design). Top and bottom of wall design to be covered in duco painted louvers(as per design). Mirror and metallic properties in PU paint finish are included in the design.			
D	AUTOMATIC TELESCOPIC SLIDING			2,26,180
1	Providing and fixing of Automatic Telescopic(with 1 fix and 1 slider) system including Fluted Glass, 10mm plain toughened glass and bend profile.			
Total cost A				6,68,080

	NURSE STATION			
D	ELEVATION	103sq.ft	950/sq.ft	97,850
1	Base of wall panelling in 16.50mm MDF of Century Prowood or Action Tesa company bolted with the help of sawthread screws of best quality on base of panelling.			
2	Top finish includes fluted panels in PU finish with mixture of laminate and metal profile.			
3	Open shelves in PU finish and bottom storage in laminate finish.			
	Total cost B			97,850
	VIP LOUNGE			
E	ELEVATION	128sq.ft	950/sq.ft	1,21,600
1	Base of wall panelling in 16.50mm MDF of Century Prowood or Action Tesa company bolted with the help of sawthread screws of best quality on base of panelling.			
2	Top finish includes long heighted panels in MDF with CNC work on it (as per design) and to be painted in PU finish after CNC (as per design).			
3	Center panel in laminate finish with metal profiles and aluminium profiles for lights(as per design).			
F	ELEVATION	128sq.ft	950/sq.ft	1,21,600
1	Base of wall panelling in 16.50mm MDF of Century Prowood or Action Tesa company bolted with the help of sawthread screws of best quality on base of panelling.			
2	Top finish includes PU Paint with matt finished metal profile, display rack in laminate finish and LED panel storage in laminate finish.			
	Total cost C			2,43,200
	ELECTRICAL PANEL			
G	ELEVATION	35sq.ft	950/sq.ft	33,250.00
1	Base of wall panelling in 16.50mm MDF of Century Prowood or Action Tesa company bolted with the help of sawthread screws of best quality on base of panelling.			
2	Top finish includes charcoal moldings in European pattern with PU paint.			
3	Electrical panel wall background in wallpaper finish.			
	Total cost D			33,250.00

	TREATMENT ROOMS			
I	ELEVATION	60sq.ft	180/sq.ft	10,800.00
1	Base of wall panelling in 16.50mm MDF of Century Prowood or Action Tesa company bolted with the help of sawthread screws of best quality on base of panelling.			
2	Top finish in wallpaper as selected.			
2	ELEVATION	73sq.ft	180/sq.ft	13,140.00
1	Base of wall panelling in 16.50mm MDF of Century Prowood or Action Tesa company bolted with the help of sawthread screws of best quality on base of panelling.			
2	Top finish in wallpaper as selected.			
3	ELEVATION	49sq.ft	180/sq.ft	8,820.00
1	Top finish includes wallpaper finish.			
	NOTE: WALL PAINT IS NOT INCLUDED			
	Total cost E			32,760
	WINDOW BLINDS			
	WAITING LOUNGE	24sq.ft	200/sq.ft	4,800.00
2	CONSULTANCY ROOM 1	24sq.ft	200/sq.ft	4,800.00
3	CONSULTANCY ROOM 2	24sq.ft	200/sq.ft	4,800.00
4	CONSULTANCY ROOM 3	24sq.ft	200/sq.ft	4,800.00
5	CONSULTANCY ROOM 4	24sq.ft	200/sq.ft	4,800.00
6	CONSULTANCY ROOM 5	24sq.ft	200/sq.ft	4,800.00
	NOTE: INCLUDE RS. 300 PER BLIND AS FITTING CHARGES			1,800.00
	Total cost F			30,600.00
	TOTAL COST OF WORK----- A+B+C+D+E+F =			11,05,740
	GRAND TOTAL			11,05,740
		SAY		11.5 Lacs
	RUPEES ELEVEN LACS AND FIVE THOUSAND ONLY.			